

“ Another successful project by TecGates Engineering ”

Contribution in the Indonesian Power Generation Sector

Turnkey EPCC contractor of the Coal Handling System for Jawa Tengah PLTU1 Power Plant in Central Java, Indonesia

Material Handled : Coal

Delivery Time : 18 months

TOTAL ENGINEERING AND EQUIPMENT SUPPLY

1. Ship Unloader : 1750 TPH, Grab Type
2. Stacker / Reclaimer : 1750 TPH / 1000 TPH
3. Conveyor Systems : 12 units at 1750 TPH, 3.42km total length
4. Dust Suppressant : For storage yard, 80 meters coverage
5. Sampler System : Before and after crushing
6. Crushing Station : 1000 TPH, 30mm output
7. Coal Bunkers : 10 units, 420 tons each



TecGates Engineering (M) Sdn Bhd (254230-H)

For more information, please contact **+603 2721 4970**



www.tecgates.com.my